



DEPARTMENT OF PUBLIC WORKS
 Maple Street Annex
 725 Maple Street · PO Box 100
 Hillsboro, Missouri 63050
 (636) 797-5340

Last Updated: 08/06/2020

PUBLIC INFORMATION SHEET

- 1. **Project Identification:** Antire Road at Williams Creek Road Intersection Improvements. Project No. STP-5460 (604)
- 2. **Resident Engineer:** Brian Dugan
- 3. **County’s Representative:** Tom Compton
- 4. **County’s Consultant:** N/A
- 5. **Council District:** District 1
- 6. **Approximate Date for Approved Final Plans:** Winter 2019
- 7. **Additional Right-Of-Way Required:** Yes
- 8. **Approximate Date of Right-Of-Way Acquisition:** Spring 2018
- 9. **Length of Road or Bridge:** 1005 ft. of roadway
- 10. **Bridge Rating and Load Posting:** N/A
- 11. **Contract Amount:** \$342,220.00
- Low Bid:** Yes
- Funding:** 80% Federal and 20% Local
- 12. **Contractor:** Gershenson Construction Co.
- 13. **Number of Working Days:** 40
- 14. **Estimated Construction Starting Date:** Summer 2020
- 15. **Estimated Completion Date:** Fall 2020

16. Miscellaneous Information (location, description of work, detour roads, utilities relocation, message boards, shoulder width, etc.):

The project in general will consist of a realignment of the intersection. The purpose is to eliminate the “S” curve on Antire and bring Williams Creek into Antire at an acceptable approach angle(80 degrees). In addition, vertical geometric improvements will be made which will further improve sight distance. Located at the intersection of Antire Road at Williams Creek Road, in Section 14, Township 43 North, Range 4 East, Jefferson County, Missouri.

